Bruhath Bangalore Mahanagara Palike Dasarahalli Zone

Excecutive Engineer, Project division

SCHEDULE - B

Name of Work: Improvements to Roads and Footpaths Pipeline Road at Mallasandra Colony in Mallasandra Ward No 13 Shettyhalli Sub Division.

Name of the Contractor:Technical Manager, KRIDL

Sl No	Description of Items	Unit	Sanctioned	
			Qty	Rate
1	**Earthwork excavation by manual means** in ordinary soil invoiving in average horizontal throw up to 2m & an average lift upto 1.5m, excavated surface leveled & sides neatly dressed, the disposed earth to be levelled neatly after breaking of clods complete as per specification.	Cum	101.77	175.96
2	Providing and fixing Pre cast solid concrete kerb stones made out of CC1:2:4 and finished with CM 1:3 plastering and finishing cutting etc., complete.	~~Cum~~ Nos.	1101.00	385.84
3	Removing B S Slab Drain And Stacking	Sqm	88.43	65.72
4	Providing and laying in position plain cement concrete of mix 1:4:8 with OPC cement @ 180kgs, with 40mm and down size graded granite metal coarse aggregates @0.85cum and fine aggregates @ 0.57cum machine mixed, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation, including cost of all materials, labour, HOM of machinery, curing complete as per specifications.	Cum	5.64	4443.52
			4.68	5159.02
5	Providing and laying in position plain cement concrete of mix 1:4:8 with OPC cement @ 180kgs, with 40mm and down size graded granite metal coarse aggregates @0.85cum and fine aggregates @ 0.57cum machine mixed, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation, including cost of all materials, labour, HOM of machinery, curing complete as per specifications.	Cum	70.75	5159.02
6	Proveding and Laying plain reinforced cement concrete for side drains using m20 nominul mix concrete with OPC cement 300kgs. With 20mm and down size ganite metal course aggregates @0.69cum and fine aggregates @0.43cum machine mixed,well compacted for walls and bottom including centring,shuttring,cost of materails, HOM of machinaries. Complete Excluding cost of steel asper MORTH Specification no1500,1700,2200. Wall And Bottom thickness 15cm	Cum	69.04	11032.48
7	Providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications.Specification No. KBS 4.6.3, TMT bars Fe 500.	Tonnes	1.24	64243.42
8	Providing & laying reinforeced cement precast slabs of mix CC 1:11/2:3 using 20mm & down size graded Granite metal using HYSD 10mm dia steel @ 100mm c/c both ways & Complete as per specfications.	SqM Cum	361.98	1957.00

EXECUTIVE ENGINEER-4
KRIDL, BBMP DIVISION
BENGALURU-560 010

Executive Engineer
Project Division
Dasarahalli Zone, BBMP

Scanned by CamScanner

9	Painting two coats after filling the surface with synthetic enamel paint in approved shades on new plastered concrete surfaces, with materials, labour complete as per specifications. MORTH Chapter 8	Sqm / Cum	580.06	63.6
10	Providing and constructing **load bearing wall** with solid concrete blocks of size 400x150x200 mm having block density not lessthan 1800 kg/m3 and having a minimum average compressive strength 5.00 N/mm2 confirming to IS 2185 (Part) : 2005 and constructed with CM 1:4 , as per IS 2572:2005 including cost of all materials, labour charegs, scaffolding, curing complete as per specifications.	Sqm	242.4	880.86
11	Providing and laying in position plain cement concrete of mix 1:2:4 with cement @ 240kgs, with 20mm and down size graded granite metal coarse aggregates @ 0.69 cum and fine aggregtes @ 0.459cum, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation, plinth and cills, ncluding cost of all materials, labour, HOM of machinery, curing complete as per specifications.	Cum	6.82	5767.46

EXECUTIVE ENGINEER-4
KRIDL, BBMP DIVISION
BENGALURU-560 010

CONTRACTOR

Executive Engineer
Project division
Dasarahalli Zone, BBMP

Scanned by CamScanner